

HO-1081

8680 Pine Road
Private

Description:

The house at 8680 Pine Road is a one-story, three-bay by one-bay cottage with a rubble stone foundation topped by several courses of brick, asbestos shingle siding, and a gable roof with asphalt shingles and a northeast-southwest ridge. There is a one-story, one-bay by one-bay ell on the rear with the same materials and the gable roof has a northwest-southeast ridge. It has a shed-roofed addition on the southwest that appears to be an enclosed porch, with a parged foundation and the same siding and roofing, and a smaller shed-roofed addition on the northwest, also with a parged foundation and the same siding and roofing. The southeast elevation has a three-bay flat-roofed porch of aluminum with iron posts and a concrete deck on a stone-veneered foundation. About 15 feet northwest of the house is a log outbuilding that is one story and one bay by one bay. It is built of round logs with saddle notches.

Significance:

The house at 8680 Pine Road is typical of second-quarter of the twentieth century blue-collar, owner-occupied housing at its simplest. It reflects national trends in house design, also at its simplest. Given its proximity to Guilford, which historically was an African-American community, it is likely that this house was built by, and for, a black Howard County family. The assessments records state that the house was built in 1950, and there seems no good reason to question this date. The house may be built on part of an earlier foundation, however, which would explain the use of several courses of brick on top of the stone. The log outbuilding was likely built in the same period, probably by the owner using readily available local timber. It is of interest for its similarity to Adirondack log buildings that became popular in this country in the late nineteenth century for resort architecture. This building type filtered down to log structures for individual homes and businesses in Howard County, and it worked for small outbuildings, as well. Several of these buildings have been documented along the Route 1 corridor. The house was scheduled to be demolished in late 2011 or early 2012 for new development.

Maryland Historical Trust

Maryland Inventory of Historic Properties Form

Inventory No. HO-1081

1. Name of Property

(indicate preferred name)

historic

other

2. Location

street and number 8680 Pine Road

not for publication

city, town Jessup

☒ vicinity

county Howard

3. Owner of Property

(give names and mailing addresses of all owners)

name Pine Road LLC

street and number 6800 Deerpath Rd, Suite 150

telephone

city, town Elkridge

state MD

zip code 21075

4. Location of Legal Description

courthouse, registry of deeds, etc. Howard County Courthouse

liber 13637 folio 61

city, town Ellicott City

tax map 47

tax parcel 668

tax ID number

5. Primary Location of Additional Data

- ☐ Contributing Resource in National Register District
☐ Contributing Resource in Local Historic District
☐ Determined Eligible for the National Register/Maryland Register
☐ Determined Ineligible for the National Register/Maryland Register
☐ Recorded by HABS/HAER
☐ Historic Structure Report or Research Report at MHT
☐ Other: _____

6. Classification

Category	Ownership	Current Function		Resource Count	
<input type="checkbox"/> district	<input type="checkbox"/> public	<input type="checkbox"/> agriculture	<input type="checkbox"/> landscape	Contributing	Noncontributing
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> commerce/trade	<input type="checkbox"/> recreation/culture	2	0 buildings
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> defense	<input type="checkbox"/> religion	0	0 sites
<input type="checkbox"/> site		<input type="checkbox"/> domestic	<input type="checkbox"/> social	1	0 structures
<input type="checkbox"/> object		<input type="checkbox"/> education	<input type="checkbox"/> transportation	0	0 objects
		<input type="checkbox"/> funerary	<input type="checkbox"/> work in progress	3	0 Total
		<input type="checkbox"/> government	<input type="checkbox"/> unknown		
		<input type="checkbox"/> health care	<input checked="" type="checkbox"/> vacant/not in use	Number of Contributing Resources previously listed in the Inventory	
		<input type="checkbox"/> industry	<input type="checkbox"/> other: _____	0	

7. Description

Inventory No. HO-1081

Condition

<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated
<input type="checkbox"/> good	<input type="checkbox"/> ruins
<input checked="" type="checkbox"/> fair	<input type="checkbox"/> altered

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

The house at 8680 Pine Road is located on the northwest side of the road and faces southeast toward the road, between Guilford and Savage in southeastern Howard County, Maryland. The house is a one-story, three-bay by one-bay cottage with a rubble stone foundation topped by several courses of brick, asbestos shingle siding, and a gable roof with asphalt shingles and a northeast-southwest ridge. There is a one-story, one-bay by one-bay ell on the rear with the same materials and the gable roof has a northwest-southeast ridge. It has a shed-roofed addition on the southwest that appears to be an enclosed porch, with a parged foundation and the same siding and roofing, and a smaller shed-roofed addition on the northwest, also with a parged foundation and the same siding and roofing. The house has a parged brick chimney in the center of the main block and an exterior CMU chimney on the northwest gable end of the ell.

The southeast elevation has a door set just east of center with one light over four square panels. The end bays have a boarded-up window. There is a three-bay flat-roofed porch of aluminum with iron posts and a concrete deck on a stone-veneered foundation. The southwest elevation has a boarded-up window set just south of center, with a louvered vent in the gable end. The enclosed porch has a modern door and a boarded-up window. The northwest addition has a small one-light window set high on the wall of the northwest elevation, and the ell has a louvered vent in the gable end. The northeast elevation of the main block has a window set just east of center with a one-over-one sash, and a louvered vent in the gable end. The ell has a boarded-up window.

About 15 feet northwest of the house is a log outbuilding that is one story and one bay by one bay. It is built of round logs with saddle notches, and has a gable roof with asphalt shingles and a northwest-southeast ridge. The gable ends have wood weatherboards. The southeast elevation has a vertical board door. There are shed-roofed frame additions on the northeast, southwest, and northwest; the latter is mostly collapsed.

About 75 feet west of the house is a brick structure that is about 18 inches high and open on the top and on the west end. The east end is rounded. The bricks are set in Portland cement, and there are some stones in the foundation at the west end. This appears to have been used as an incinerator, for controlled burning.

8. Significance

Inventory No. HO-1081

Period	Areas of Significance	Check and justify below			
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> health/medicine	<input type="checkbox"/> performing arts	
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> archeology	<input type="checkbox"/> education	<input type="checkbox"/> industry	<input type="checkbox"/> philosophy	
<input type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> engineering	<input type="checkbox"/> invention	<input type="checkbox"/> politics/government	
<input checked="" type="checkbox"/> 1900-1999	<input type="checkbox"/> art	<input type="checkbox"/> entertainment/	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion	
<input type="checkbox"/> 2000-	<input type="checkbox"/> commerce	<input type="checkbox"/> recreation	<input type="checkbox"/> law	<input type="checkbox"/> science	
	<input type="checkbox"/> communications	<input type="checkbox"/> ethnic heritage	<input type="checkbox"/> literature	<input type="checkbox"/> social history	
	<input type="checkbox"/> community planning	<input type="checkbox"/> exploration/	<input type="checkbox"/> maritime history	<input type="checkbox"/> transportation	
	<input type="checkbox"/> conservation	<input type="checkbox"/> settlement	<input type="checkbox"/> military	<input type="checkbox"/> other: _____	

Specific dates N/A

Architect/Builder N/A

Construction dates c. 1925-50

Evaluation for:

☐ National Register

☐ Maryland Register

☒ not evaluated

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance projects, complete evaluation on a DOE Form – see manual.)

The house at 8680 Pine Road is typical of second-quarter of the twentieth century blue-collar, owner-occupied housing at its simplest. It reflects national trends in house design, also at its simplest. Given its proximity to Guilford, which historically was an African-American community, it is likely that this house was built by, and for, a black Howard County family. The assessments records state that the house was built in 1950, and there seems no good reason to question this date. The house may be built on part of an earlier foundation, however, which would explain the use of several courses of brick on top of the stone. The log outbuilding was likely built in the same period, probably by the owner using readily available local timber. It is of interest for its similarity to Adirondack log buildings that became popular in this country in the late nineteenth century for resort architecture. This building type filtered down to log structures for individual homes and businesses in Howard County, and it worked for small outbuildings, as well. Several of these buildings have been documented along the Route 1 corridor. The house was scheduled to be demolished in late 2011 or early 2012 for new development.

9. Major Bibliographical References

Inventory No. HO-1081

10. Geographical Data

Acreage of surveyed property 1.83 A
Acreage of historical setting 1.83 A
Quadrangle name Savage

Quadrangle scale: 1:24000

Verbal boundary description and justification

The boundaries consist of the outlines of the property, tax map 47, parcel 668, which encompasses all of the historic buildings and features on the site.


11. Form Prepared by

name/title	Ken Short		
organization	Howard County Department of Planning & Zoning	date	March 2012
street & number	3430 Courthouse Drive	telephone	410-313-4335
city or town	Ellicott City	state	MD

The Maryland Inventory of Historic Properties was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
DHCD/DHCP
100 Community Place
Crownsville, MD 21032-2023
410-514-7600



HO-1081

8680 Pine Road
Savage quad

HO-1081

8680 Pine Road
Howard County, Maryland
Ken Short, photographer

Photo Log

Nikon D-70 camera
HP Premium Plus paper
HP Gray Photo print cartridge

HO-1081_2012-01-17_01
House, southeast elevation

HO-1081_2012-01-17_02
House, northeast & northwest elevations

HO-1081_2012-01-17_03
Outbuilding, southeast elevation



HO-1081

8680 Pine Road

Howard County, Maryland

Ken Short

2012-01-17

MD SHPO

House, southeast elevation

1 of 3



HO-1081

8680 Pine Road

Howard County, Maryland

Ken Short

2012-01-17

MD SHPO

House, northeast + northwest elevations

2 of 3



HO-1081

8680 Pine Road

Howard County, Maryland

Ken Short

2012-01-17

MD SHPO

Outbuilding, southeast elevation

3 of 3